FRENCH ROCKS DIVISION.

ADVERTISEMENT.

The ——December 1892.

Tenders are hereby invited for improving the Amani Kikkere Tank, Registered No. 191, Krishnarajpete Taluk.

2. The plans, estimates, schedule of rates and conditions may be seen at the Executive Engineer's Office between the hours of 11 A. M. and 4 P. M. daily.

3. Printed forms of tender will be supplied on application, free of cost, by the Executive Engineer. These forms should be filled in, signed by the contractor and forwarded in sealed covers to the Executive Engineer before the 15th January 1893. An approximate estimate of the quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1894.

4. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. No tenders will be received unless accompanied by a deposit of Rs. 100 as earnest money.

6. Within 8 days of the acceptance of the tender, the contractor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be taken to meet any loss that may be sustained by Government.

7. The name of the contractor whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries respecting the acceptance or rejection of a tender will receive any reply whatever.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned to applicants in due course.

Items of Work.	Per.	Quantity.
Bund—		
Earthwork	C. Yd.	1,357
Do	Do	6,732
Old stone work	Do	300
New stone work	Do	432
Grade stones (fixing charge)	Each.	45
Tank No. Stone	Do	1
Gauge Stone	Do	1
Sluice—		
Constructing rear cistern	L. S.	Rupees.
Left Waste Weir, 150 *feet*—		
Rough stone removal	C. Yd.	58
Dismantling present body wall	Do	50
Excavation in earth	Do	7
Do in soft rock	Do	371
Stone in surki mortar, hearting	C. Ft.	8,816
Do hammer dressed	Do	1,621
Brick in surki mortar	Do	3,677
Plastering with chunam	Sqr.	16·26
Pointing with Portland cement	Do	7·14
Stone slabs	C. Ft.	373
Concrete	Do	350
Benching rock	R. Ft.	180
Constructing a sluice ($1 \times 1\frac{1}{2}$)	L. S.	Rupees.
Right Weir Channel—		
Excavation in soft rock	C. Yd.	300
Earthwork for training bank	Do	3,152
Repairing present aqueduct	L. S.	Rupees.

D. SITARAM RAO,
Executive Engineer.